

**INSTITUTO DE CIENCIAS DE
LA CONSTRUCCIÓN
EDUARDO TORROJA**


C/ Serrano Galvache nº 4
28033 Madrid

Tel.: (34) 91 302 04 40

Fax: (34) 91 302 07 00

director@ietcc.csic.es

www.ietcc.csic.es



MIEMBRO DE LA EOTA

EUROPEAN TECHNICAL APPROVAL

ETA – 07/0242

(English language translation, the original version is in Spanish language)

Nombre comercial:

Trade name:

MAXELASTIC

Beneficiario del DITE

Holder of approval:

DRIZORO, S.A

**C/ Primavera nº50-52, Polígono Industrial Las Monjas
28850 TORREJÓN DE ARDOZ - MADRID (España)**

Área genérica y uso del producto de construcción :

Generic type and use of construction product:

Sistemas de Impermeabilización de Cubiertas Aplicados en forma Líquida, basados en Polímeros en Dispersión Acuosa

Liquid Applied Roof Waterproofing Kits, based on Water Dispersible polymers

Validez de :

hasta :

Validity from / to:

24 / 06 / 2013

24 / 06 / 2018

This ETA replaces the previous one with the date of 12/09/07 to 12/09/12

Plantas de fabricación:

Manufacturing plant:

**C/ Primavera nº50-52, Polígono Industrial Las Monjas
28850 TORREJÓN DE ARDOZ - MADRID (España)**

El presente Documento de Idoneidad Técnica Europeo contiene:

This European Technical Approval contains:

7 páginas, incluyendo 1 anexo, el cual forma parte del documento

7 pages including 1 annex which form an integral part of the document



Organización Europea para la Idoneidad Técnica
European Organisation for Technical Approvals



I. LEGAL BASES AND GENERAL CONDITIONS

1. This European Technical Approval is issued by the **Instituto de Ciencias de la Construcción Eduardo Torroja (IETcc)** in accordance with:
 - Council Directive (89/106/EEC) of 21 December 1988 on the approximation of laws, regulations and administrative provisions of Member States relating to construction products⁽¹⁾, modified by the Council Directive 93/68/EEC of July 1993⁽²⁾ and Regulation (EC) n° 1882/2003 of the European Parliament and of the Council⁽³⁾.
 - *Real Decreto 1630/1992 de 29 de diciembre, por el que se dictan disposiciones para la libre circulación de productos de construcción en aplicación de la Directiva 89/106/CEE⁽⁴⁾. REAL DECRETO 1328/1995, de 28 de julio, por el que se modifican, en aplicación de la Directiva 93/68/CEE las disposiciones para la libre circulación, aprobadas por el Real Decreto 1630/1992, de 29 de diciembre. (B.O.E. 19.895) y la Orden CTE/2276/2002 de 4 de septiembre.*
 - Common Procedural Rules for Requesting, Preparing and the Granting of European Technical Approvals set out in the Annex of Commission Decision 94/23/EC⁽⁵⁾.
 - Guideline for European Technical Approval of Liquid applied roof waterproofing kits, ETAG 005, edition 2000, Part 1 "General" and Part 8 "Specific stipulations for kits based on water dispersible polymers".
2. The **Instituto de Ciencias de la Construcción Eduardo Torroja** is authorised to check whether the provisions of this European Technical Approval are met. Checking may take place in the manufacturing plant(s). Nevertheless, the responsibility for the conformity of the products to the European Technical Approval and for their fitness for intended use remains with the holder of the European Technical Approval.
3. This European Technical Approval is not to be transferred to other manufacturers or agents of manufacturers other than those indicated on page 1, or manufacturing plants other than those laid down in the context of this European Technical Approval.
4. This European Technical Approval may be withdrawn by the **Instituto de Ciencias de la Construcción Eduardo Torroja** pursuant to Article 5.1 of the Council Directive 89/106/EEC.
5. Reproduction of this European Technical Approval including transmission by electronic means shall be in full. However, partial reproduction can be made with the written consent of the **Instituto de Ciencias de la Construcción Eduardo Torroja**. In this case partial reproduction has to be designated as such. Texts and drawings of advertising brochures shall not contradict or misuse the European Technical Approval.
6. The European Technical Approval is issued by the Approval Body in its official language. This version corresponds to the version circulated within EOTA. Translations into other languages have to be designated as such.

¹ Official Journal of the European Communities n° L 40, 11.2.1989, p.12

² Official Journal of the European Communities n° L 220, 30.8.1993, p.1

³ Official Journal of the European Communities n° L 284, 31.10.2003, p.25

⁴ Boletín Oficial del Estado n° 34 de 9 de febrero de 01993.

⁵ Official Journal of the European Communities n° L 17, 20.1.1994, p.34



II. SPECIFIC CONDITIONS OF THE EUROPEAN TECHNICAL APPROVAL

1. Definition of product and intended use

Definition of product. The liquid applied roof waterproofing kit, based on water dispersible polymers "MAXELASTIC", manufactured by the company DRIZORO, S.A., consists of a water dispersible styrene - acrylic copolymers, with loads and pigments mineral, and additives (anti-air entering, biocides, etc.); which once polymerised conforms an elastic lining, in form of a layer completely bonded to the support (concrete, mortar, ceramic).

The minimum layer thickness of the assembled system has to be 1,7 mm and the quantity consumed larger than 3 kg/m². The annex 1 shows the components and the system build-up of the system.

Intended use. The intended use of this System is the waterproofing of roof against the water, as in liquid as vapour form. This LARWK fulfils the Essential Requirements nº 2 (Safety in case of fire), nº 3 (Hygiene, health and the environment) and nº 4 (Safety in use) of the Construction products directive 89/106/EEC.

The performance levels of this System according to the Guide ETAG 005⁶ Part. 1 and Part. 8 are included in the annex 1. The provisions made in this European Technical Approval (ETA) are based on an assumed intended working life of the system of 10 years (W2).

The indication given on the working life cannot be interpreted as a guarantee given by the manufacturer, but are only to be regarded as a means for choosing the right products in relation to the expected economically reasonable working life of the works. "Assumed intended working life" means that, when an assessment following the ETAG provisions is made, and when this working life has elapsed, the real working life may be, in normal use conditions, considerably longer without major degradation affecting the Essential Requirements.

2. Characteristics of product and methods of verification

The assessment of the fitness of the liquid waterproofing kit MAXELASTIC for the intended use regard to the Essential Requirements nº 2, 3 and 4 was performed in compliance with the "Guideline for European Technical Approval of liquid applied roof waterproofing kits", ETAG 005, edition 2000, Part 1: General and Part 8: Specific stipulations for kits based on water dispersible polymers.

According to manufacture's declaration placed at IETcc, the components of the system MAXELASTIC does not contain dangerous substances defined in the EU database.

This ETA is issued for the kit "MAXELASTIC" on the basis of the product composition deposited at IETcc. Changes to the components of the kit or in the production process of the components, which could result in the production process and/or the properties of the product deposited being incorrect should be notified to IETcc before the changes are introduced. IETcc will decide whether or not such changes affect the ETA and consequently the validity of the CE marking on the basis of the ETA and if further assessment/alterations to the ETA shall be necessary.

This approval may be extended with other requirements applicable to dangerous substances resulting from transposed European legislation or applicable national regulations and administrative provisions. Besides, this approval may be extended with other requirements applicable to the products resulting from other applicable national regulations and administrative provisions. These requirements need also to be complied with.

2.1 Characteristics of System "MAXELASTIC"

2.1.1 ER. 2 Safety in case of fire

External fire performance. Clasificación: B_{roof}(t1) according to EN 13501-5.

Reaction to fire. Euroclass F: NPD

⁶ ETAG N° 5, "Liquid applied roof waterproofing kits", Official Journal of the European Communities N° C 212/02, 06.09.2002.



2.1.2 ER. 3 Hygiene, health and environment

Resistance to water vapour (EN 1931). $\mu > 1.000$

Watertightness (EOTA TR-003). Watertight

Statement of dangerous substances. According to the manufacture's declaration taking account of the EU database, the product installed does not contain and release any dangerous substance.

Resistance to wind loads (EOTA TR-4). Pass (>50 KPa)

Resistance to dynamic indentation (EOTA TR- 6).I4

Resistance to static indentation(EOTA TR-7). L4

Resistance to fatigue movement (EOTA TR-8). Pass

Resistance to low temperatures effects (-20°C). Dynamic indentation I4

Resistance to high temperatures effects (90°C).Static indentation L1

Resistance to heat ageing (EOTA TR-11). The samples are exposed to 80°C during 100 days.

Fatigue movement	pass
Dynamic indentation (-20°C)	I3
Tensile strength (MPa) (EN-ISO 527-3)	5,3
Tensile elongation (%) (EN-ISO 527-3)	77

Resistance to UV-radiation in the presence of moisture (EOTA TR- 10). The samples are exposed 2000 hours to UV-radiation.

Tensile strength (MPa) (EN-ISO 527-3)	2,5
Tensile elongation (%) (EN-ISO 527-3)	80
Dynamic indentation (-10°C)	I4

Resistance to hot water ageing (EOTA TR-12). The samples are kept in touch with water at 60°C over 30 days.

Delamination strength (kPa) (Concrete): Pass (> 50 KPa).

Static indentation :

Maximun surface temperature	Substrate	Level of resistance
90°C	Steel	L3

Resistance to plant roots (EN 13948). NPD

2.1.3 ER. 4 Safety in use

Slipperiness. NPD

2.1.4 Related aspects of serviceability

Effect of weather conditions. The system does show changes in its tensile properties, when the system is assembled and cured under two temperature conditions of 5°C and 40°C, but these values obtained complied with the manufacturer's specifications (pass).

Effect of day joints. The delamination strength test performed on an layer assembled over other one does not show an delamination strength decrease upper 20% of the value obtained in the layer assembled over the concrete support (pass).



2.2 Identification of components

The characteristics of the Waterproofing liquid (constituted by a water dispersible styrene acrylic copolymers, with loads and pigments mineral, and additives (anti-air entering, biocides, etc.)) shows the following values, which compliance with their respective tolerances stated in the Manufacturer Technical Dossier (MTD) placed at IETcc.

Density (g/cm ³)(ISO 1675)	1.250-1.350
Dry extract (105°C) (% weight) (EN 1768)	54 - 62
Ash content (450°C)(% weight) (EN 1879)	25-27

3 Evaluation of Conformity and CE marking

3.1 Attestation of Conformity System

The European Commission according to her decision (98/599/EC of October 1998, Official Journal of the European Communities N° L 287, 24.10.1998) on the procedure of attestation of conformity has laid down for this type of material **System 3** for the procedure of attestation of conformity (Annex III, clause 2(ii) second possibility of Directive 89/106/EEC) for liquid applied roof waterproofing kits. According to this decision, system 3 of Attestation of Conformity also applies with regard to external fire performance. The system 3 provides: *Tasks for the manufacturer*: Factory production control and *Tasks for the approved body*: Initial type-testing of the product.

3.2 Responsibilities

3.2.1 Tasks for the manufacturer

Factory production control. The manufacturer exercises a permanent internal control of production. All the elements, requirements and provisions adopted by the manufacturer are documented in a systematic manner in the form of written policies and procedures, including records of results performed. This production control system shall insure that the product is in conformity with this Technical European Approval.

The manufacturer shall only use incoming raw materials stated in the MTD. He shall inspect and control the raw material on acceptance with the MTD. The results of the factory production control shall be recorded and evaluated in accordance with the provisions of the "control plan"⁽⁷⁾. The records shall include at least the following information:

- Designation of the product, the basic materials and components,
- type of inspection or control,
- date of manufacture of the product, batch N° if needed, and date of inspection or control of the product or of the basic materials and components,
- result of inspections or controls and, as far as applicable, comparison with the requirements,
- signature of the person responsible for the factory production control.

The records shall be kept for at least five years. Further information concerning test, frequency and tolerance are included in the control plan, which is part of the MTD to this ETA..

Other tasks of the manufacturer. For initial type - testing of the ETICS and the components the results of the tests performed as part of the assessment for the ETA shall be used unless there are changes in the production line or plant. In such cases the necessary initial type- testing has to be agreed with the IETcc.

The manufacturer shall, on the basis of a contract, involve a body which is notified for the tasks referred to in section 3.1 in the field of the product in order to undertake the actions laid down in the clause 3.2.2. For this purpose, the control plan referred to in sections 3.2.1.1 shall be handed over by the manufacturer to the notified bodies involved.

The manufacturer shall make a declaration of conformity, stating that the construction product is in conformity with the provisions of this ETA.

⁷ The control plan is a confidential part of the European Technical Approval and only handed to the notified body involved in the procedure of attestation of conformity. The control plan has been agreed between the manufacturer and de IETcc and it is laid down in the context of the MTD and deposited at the IETcc



3.2.2 Tasks for the Approved Body

Initial type-testing of the product. The initial type-testing have been conducted by the IETcc to issued this ETA in accordance with chapter 5 of the guideline "Liquid applied roof waterproofing kits" (ETAG 005) part 1 and 8. The verifications underlying this ETA have been furnished on samples from the current production; these will replace the initial type-testing carried out by the manufacturer. The IETcc has assessed the results of these tests in accordance with chapter 6 of this ETA -Guideline, as part of the ETA issuing procedure.

3.3 CE marking

The CE marking⁽⁸⁾ shall be affixed on the pot of the kit of the roof waterproofing "MAXELASTIC". In addition to the symbol "CE" the following information shall be given:

- name or identifying mark of the manufacturer and of the factory,
- short definition of the levels of performance according to annex 1,
- the last two digits of the year in which the CE marking was affixed,
- number of the European technical approval,
- number of the Guideline for the European Technical Approval,

4. Assumptions under which the fitness for use of the product for the intended use was favorably assessed

Manufacturing. Further information about the manufacturing of the kit is laid down in MTD placed at IETcc.

Design. The fitness of the respective use for the levels of performance of this System stated in Annex 1 complies with the Spanish national requirements. In the MTD the manufacture gives information on the quantities consumed and the processing, which shall lead to a thickness of the roof waterproofing of at least the indicated in point 1.

Installation. The fitness of use of this kit can only be assumed if this is installed according to the manufacturer's instructions (part of the MTD to this ETA). Particularly, it is recommended::

- The kit installation has to carried out by qualified installers,
- it can only be used the components of the kit indicated in this ETA,
- the supervision of the amount of material used (kg/m^2) and the control visual to check that each coat cover totally the one below, can ensure the minimum thickness of the kits,
- inspection of the roof surface (cleanliness and correct preparation) before applying the roof waterproofing,
- the recommended temperature of the product to be assembled will be between 5°C and 40°C and it will be not admitted support temperatures upper to 45°C. In other conditions it will need to follow the manufacturer's instructions.

Before, the installation of MAXELASTIC, it is recommended to read its security card.

Manufacturer's responsibilities. It is responsibility of the manufacturer of the product to ensure that the information on all provisions is given to those concerned.

5 Information by the manufacture


Recommendations on packing, transport and storage. This product is not considered inflammable, so it is not necessary to follow any security instruction for transport and handle. The storage must be done at temperatures between 5°C - 45°C, in dry conditions and protected against the sun radiation. The product must be used 1 year after manufacturing date. Once the pot is opened, there is not problem to keep the rest of product for a future application, but the pot has to be perfectly closed. Further installation details are laid down in the MTD.

Recommendations on use, maintenance and repair. In those roofs with deteriorated areas of the waterproof layers, they will be repaired removing all the deteriorated layers. Afterwards, the new product will be assembled following the installation instruction and the new coats must overlap, at least 10 cm, to the coat no deteriorated. Further installation details are laid down in the MTD.

⁸ Notes on the CE marking are stated in Guidance Paper D "CE marking under the Construction Products Directive", Brussels 01 August 2002.



Instituto de Ciencias de la Construcción Eduardo Torroja
CONSEJO SUPERIOR DE INVESTIGACIONES CIENTÍFICAS
c/ Serrano Galvache nº4. 28033 Madrid. Tel: (34) 91 302 04 40 Fax. (34) 91 302 07 00
www.ietcc.csic.es



On behalf of the Instituto de Ciencias de la Construcción Eduardo Torroja


Madrid, 24 June 2013

EL DIRECTOR DEL INSTITUTO DE CIENCIAS DE LA CONSTRUCCIÓN EDUARDO TORROJA

Ángel Arteaga Iriarte

Annex 1. System build-up of the roof waterproofing "MAXELASTIC".

- A. Support
- B. 1 coat of Liquid material MAXELASTIC
- C. 2 coat of Liquid material MAXELASTIC



Characteristics of the System "MAXELASTIC"

Minimum thickness	1.7 mm
Water vapour diffusion resistant factor	$\mu > 1.000$
Resistance to wind loads	$> 50 \text{ KPa}$
Resistance to plant roots	NPD
Statement on dangerous substances	Does not contain any
Resistance to slipperiness	NPD

Performance levels according to the intended use

External fire performance	Broof (t1)
Fire reaction	NPD: class F
Expected working life	W2 (10 years)
Climatic zone of use	S (Severe)
User loads	P1
Roofs slopes	S1 – S4
Minimum surface temperatures	TL3 (- 20 °C)
Maximum surface temperatures	TH4 (90°C)